

1. KVM for VGA, keyboard, mouse goes into the top unit PC.
2. USB extender goes into bottom unit video server to extend shuttle pro.
3. Five total Cat5 into network hub. 1 from top unit, 2 from middle unit, 1 from bottom unit, 1 from controller at operating station.
4. LTC on XLR into bottom unit.
5. Three lines of genlock. Seven inputs. One output. Labeled below. 3,5,7 move 7th bnc from left. 1 or 3 output is the out
6. All video loops are color coded. left side of middle machine loop 2in and 2out together. May not have yellow loop

